



CONTROL COMMANDING L TO L+90 ACTIVATION AND CAL SEQUENCES


T. Pagano

Wednesday, February 13, 2002



L TO L+90 IS ACTIVATION AND EVALUATION PHASE







IN FIRST 90 DAYS



- Day 2: AIRS quiet and noisy buses powered on Decontamination heaters turned on
- Day 5: AIRS Group 2 power on
- Day 8,9: Power up AMSU and HSB. 1-2 days later data starts.
- Day 15: High rate starts. AIRS Scanning, VIS On, Warm Funct'l Tests
- Day 18-27: Spacecraft maneuvers
- Day 29: Earthshield deployed
- DAY 30-34: AMSU and HSB calibration tests. Switch to normal mode
- Day 36: Decontamination heaters turned off
- Day 37, 38: Initialize and turn on coolers and FPAs
- Day 39: Set Choke Point heater
- Day 39-41: Normal Mode. AIRS First Light; Start L1B Early Eval. Plan
- Day 42-48: Spacecraft maneuvers
- Days 49-67: AIRS special calibration tests (per In-Flight Cal Plan)
- Days 67-90: Switch to normal mode. L1B QA evaluations
- Day 90: L1B calibration table updates delivered



OPERATIONS READY



- Total of 102 AIRS Procedures Ready for Flight
 - · Activation, contingency shutdown, calibration, etc.
- All calibration procedures run successfully at TRW
- SCIF testing successfully tested AIRS procedures
 - Most tested live on AIRS.
 - All procs have been tested except 3. They will be tested in SCIF #4 in February
- Operators Trained and Ready



TIMELINE ASSUMPTIONS AND CONCLUSIONS



Timeline Assumptions

- Orbit achieved in time expected
- First outgassing exercise is sufficient and no others are required
- · Orbital yaw maneuvers completed prior to calibration
- No deep space maneuver

Conclusions

- Operational timeline in place.
- · Calibration sequences a key part of evaluation phase
- · ACT Ready to
 - Transfer calibration to in-orbit environment
 - Monitor and trend AIRS calibration, health and status